



Newaygo County Road Commission

935 EAST ONE MILE ROAD
WHITE CLOUD, MI 49349
Phone (231) 689-6682
Fax (231) 689-5994
www.newaygoroads.org



Find Us On Facebook

NOTICE TO BIDDERS

The Board of County Road Commissioners of Newaygo County will receive sealed bids at their office at 935 East One Mile Road, White Cloud, MI 49349, until 8:00 a.m. on Wednesday, September 23, 2026, for the following:

- Temporary Cofferdam on Spruce Ave. at Flinton Creek, Everett Township, Newaygo County

Specifications and bid forms may be obtained at the Road Commission offices during regular business hours or by visiting our website at www.newaygoroads.org

All proposals must be submitted on Road Commission furnished bid forms. Said forms must be in sealed envelopes, plainly marked as to item bid and shall bear the name of the bidder.

The Newaygo County Road Commission hereby notifies all bidders that it will affirmatively insure that in any contract entered into pursuant to this advertisement, disadvantaged business enterprise will be afforded full opportunity to submit bids in response to this invitation and will not be discriminated against on the grounds of sex, race, color or national origin in consideration for an award.

The Board reserves the right to accept or reject any or all bids, to waive any irregularities in the bids and to make award in any manner they deem to be in the best interest of Newaygo County.

BOARD OF COUNTY ROAD COMMISSIONERS
OF
NEWAYGO COUNTY

Douglas Harmon, Chairman
Lee Fetterley, Vice-Chairman
John Clark, Commissioner

Bid for Temporary Cofferdam

Spruce Ave. at Flinton Creek, Everett Township

Description: This work consists of designing, providing, installing, and removing a temporary cofferdam to provide an 80 ft long by 30 ft wide total enclosure to create a dry workspace for placement of an Aluminum Plate Box Culvert. The cofferdam must be capable of retaining water up to the design depth, allowing excavation, culvert placement, and backfilling without water ingress. Contractor will provide pumps as necessary for dewatering to maintain a dry workspace during the culvert construction (NCRC to maintain pumps during culvert construction). Contractor is responsible for excavation and placement of wrapped MDOT 6A in Mirafi 140N geotextile or equivalent culvert bedding with an invert of 858.0 ft to the culvert invert elevation of 859.5 ft. See plan sheets for details and geotechnical report. It is highly recommended to visit the site prior to bidding.

NCRC Responsibility: Top of cofferdam sheeting shall be driven to an elevation set by NCRC. EGLE Permit, Excavation of diversion channel, Excavation for Existing Culvert Removal, Aluminum Plate Box Culvert installation and backfill, maintenance of dewatering pumps during culvert construction, and road reconstruction will be handled by NCRC

Time and Duration: This work shall take place June 2027.

Specifications: Placement of temporary cofferdam shall be performed according to 2020 Michigan Department of Transportation Standard Specifications for Construction, Section 704, and 906

Insurance Requirements:

1. To the fullest extent permitted by law, the Contractor shall indemnify and hold harmless the Newaygo County Road Commission and its agents and employees from and against all claims, damages, losses and expenses including, but not limited to, attorneys' fees arising out of or resulting from the performance of this Contract including claims,

damages, losses and expenses attributable to bodily injury, sickness, disease or death, or to injury to or destruction of tangible property, but only to the extent caused by the fault, negligent acts, or omissions of the Contractor, a Subcontractor, anyone directly or indirectly employed by them or anyone for whose acts they may be liable, regardless of whether or not such claim, damage loss or expense is caused in part by the parties indemnified hereunder. This obligation does not include an obligation to indemnify the parties, indemnified hereunder for their sole negligence and shall not be construed to negate or modify other rights or obligations of indemnity that otherwise exist as to the parties or persons described herein, arising out of and during the progress and to the completion of work all in accordance with Public Act 468 of 2012 and the 2012 Michigan Department of Transportation's "Standard Specifications for Construction", Division 1, paragraph 1.07.10 with the following minimum requirements:

Workman's Compensation Statutory Coverage

Bodily Injury and Property Damage Other Than Automobile:

Each Occurrence \$1,000,000

Aggregate \$2,000,000

Bodily Injury Liability and Property Damage Liability Automobile:

Bodily Injury Liability \$500,000 Each Person,
Each Occurrence \$1,000,000

Property Damage Liability \$1,000,000 Each Occurrence

Combined Single Limit for Bodily Injury and Property Damage Liability

Each Occurrence \$2,000,000

Insurance Certificate declaring Newaygo County Road Commission as additional insured, not certificate holder, must be issued and shall become part of the contract.

2. Contractor shall maintain current up-to-date insurance coverage during the term of the contract and failure to do so shall result in termination of said contract.

3. Certificate must be submitted within fifteen days upon notification of award of Contract and prior to Contract signing.

Submission of bid will be construed as a conclusive presumption that the Contractor is thoroughly familiar with the bid requirements and specifications and that he/she understands and agrees to abide by each and all of the stipulations and requirements contained therein.

Measurement and Payment: Cofferdam shall be paid as a lump sum. The unit price for cofferdam includes designing, providing, installing, maintaining, dewatering, excavation and placement of Wrapped MDOT 6A in mirafi 140N geotextile or equivalent culvert bedding, and removing sheet pile cofferdam after NCRC culvert construction.

Questions should be directed to Mike Brege, Superintendent, Newaygo County Road Commission or Derek Wawczyk, Manager, Newaygo County Road Commission at (231)-689-6682.

BID FORM – Temporary Cofferdam Flinton Creek at Spruce Ave.

DUE BY 8:00a.m. on Wednesday, September 23, 2026

Submitted to:

Newaygo County Road Commission

935 East One Mile Road

White Cloud, MI 49349

Fax: 231-689-5994

admin@newaygoroads.org

Cofferdam shall be paid as a lump sum (includes all Labor, Equipment, and Materials). The unit price for cofferdam includes designing, providing, installing, maintaining, dewatering, excavation and placement of Wrapped MDOT 6A in mirafi 140N geotextile or equivalent culvert bedding, and removing sheet pile cofferdam after NCRC culvert construction.

▪ **Lump Sum TOTAL:**

\$ _____

Contractor Signature: _____

Printed Name and Title: _____

Company: _____

Address: _____

City, State, ZIP: _____

Telephone Number: _____

Fax Number: _____

E-Mail Address: _____